

# Summary of Modifications/Changes in this Update

This Summary of Changes is for information only.  
It is not a part of the referenced document, and should not be used for project documentation.

U.S. Department of Veterans Affairs ♦ Office of Construction & Facilities Management

## NUMBER, DATE, AND TIL EFFECTIVE DATE OF THIS VERSION:

v3.1 July 1, 2021 Effective: August 1, 2021

## TITLE OF DOCUMENT:

OIT Infrastructure Standard for Telecommunications Spaces

## NUMBER, DATE, AND TIL EFFECTIVE DATE OF VERSION BEING SUPERSEDED (old):

v3.0 August 21, 2020 Effective: October 1, 2020

## DESCRIPTION OF DOCUMENT (previous title, number, other identifying data):

Not Applicable

## SUMMARY OF CHANGES IN THIS VERSION:

1. **4.2.8 Bonding and Grounding** | Changed “supplementary” ground path to “dedicated”.
2. **4.4.4 Fiber Optic Cable** | Relaxed authorization for Universal Cassettes to be used when breaking out to LC connectors.
3. **Appendix B, Sheet 2** | Corrected split package air conditioner heat rejection requirement to be 17,000 BTU/h (5 kW) per rack.
4. **Appendix B, Sheet 3** | Corrected PDF layer issue masking attributes and specifications in the table.
5. **Appendix B, Sheet 21** | Corrected PDF layer issue masking a PDU on the left side of Plate 1.